









Living Building Challenge Materials Specified Products











**SECTION 1405
INSTALLATION OF WALL COVERINGS**

1405.1 General. Exterior wall coverings shall be designed and constructed in accordance with the applicable provisions of this section.

1405.2 Weather protection. Exterior walls shall provide weather protection for the building. The materials of the minimum nominal thickness specified in Table 1405.2 shall be acceptable as approved weather coverings.

1405.3 Vapor retarders. Class I or II vapor retarders shall be provided on the interior side of frame walls in Zones 5, 6, 7, 8 and Marine 4.

Exceptions:


1. Basement walls.
2. Below-grade portion of any wall.
3. Construction where moisture or its freezing will not damage the materials.


1405.3.1 Class III vapor retarders. Class III vapor retarders shall be permitted where any one of the conditions in Table 1405.3.1 is met.

**TABLE 1405.3.1
CLASS III VAPOR RETARDERS**

ZONE	CLASS III VAPOR RETARDERS PERMITTED FOR: ^a
Marine 4	Vented cladding over OSB Vented cladding over plywood Vented cladding over fiberboard Vented cladding over gypsum Insulated sheathing with <i>R</i> -value \geq R2.5 over 2x4 wall Insulated sheathing with <i>R</i> -value \geq R3.75 over 2x6 wall
5	Vented cladding over OSB Vented cladding over plywood Vented cladding over fiberboard Vented cladding over gypsum Insulated sheathing with <i>R</i> -value \geq R5 over 2x4 wall Insulated sheathing with <i>R</i> -value \geq R7.5 over 2x6 wall
6	Vented cladding over fiberboard Vented cladding over gypsum Insulated sheathing with <i>R</i> -value \geq R7.5 over 2x4 wall Insulated sheathing with <i>R</i> -value \geq R11.25 over 2x6 wall
7 and 8	Insulated sheathing with <i>R</i> -value \geq R10 over 2x4 wall Insulated sheathing with <i>R</i> -value \geq R15 over 2x6 wall

For SI: 1 pound per cubic foot = 16 kg/m³.
 a. Spray foam with a minimum density of 2 lbs/ft³ applied to the interior cavity side of OSB, plywood, fiberboard, insulating sheathing or gypsum is deemed to meet the insulating sheathing requirement where the spray foam *R*-value meets or exceeds the specified insulating sheathing *R*-value.





**SECTION 1405
INSTALLATION OF WALL COVERINGS**

1405.1 General. Exterior wall coverings shall be designed and constructed in accordance with the applicable provisions of this section.

1405.2 Weather protection. Exterior walls shall provide weather protection for the building. The materials of the minimum nominal thickness specified in Table 1405.2 shall be acceptable as approved weather coverings.

1405.3 Vapor retarders. Class I or II vapor retarders shall be provided on the interior side of frame walls in Zones 5, 6, 7, 8 and Marine 4.

Exceptions:

1. Basement walls.
2. Below-grade portion of any wall.
3. Construction where moisture or its freezing will not damage the materials.

1405.3.1 Class III vapor retarders. Class III vapor retarders shall be permitted where any one of the conditions in Table 1405.3.1 is met.

**TABLE 1405.3.1
CLASS III VAPOR RETARDERS**

ZONE	CLASS III VAPOR RETARDERS PERMITTED FOR: ^a
Marine 4	Vented cladding over OSB Vented cladding over plywood Vented cladding over fiberboard Vented cladding over gypsum Insulated sheathing with <i>R</i> -value \geq R2.5 over 2x4 wall Insulated sheathing with <i>R</i> -value \geq R3.75 over 2x6 wall
5	Vented cladding over OSB Vented cladding over plywood Vented cladding over fiberboard Vented cladding over gypsum Insulated sheathing with <i>R</i> -value \geq R5 over 2x4 wall Insulated sheathing with <i>R</i> -value \geq R7.5 over 2x6 wall
6	Vented cladding over fiberboard Vented cladding over gypsum Insulated sheathing with <i>R</i> -value \geq R7.5 over 2x4 wall Insulated sheathing with <i>R</i> -value \geq R11.25 over 2x6 wall
7 and 8	Insulated sheathing with <i>R</i> -value \geq R10 over 2x4 wall Insulated sheathing with <i>R</i> -value \geq R15 over 2x6 wall

For SI: 1 pound per cubic foot = 16 kg/m³.
 a. Spray foam with a minimum density of 2 lbs/ft³ applied to the interior cavity side of OSB, plywood, fiberboard, insulating sheathing or gypsum is deemed to meet the insulating sheathing requirement where the spray foam *R*-value meets or exceeds the specified insulating sheathing *R*-value.

1405.3.2 Material vapor retarder class. The vapor retarder class shall be based on the manufacturer's certified testing or a tested assembly.

The following shall be deemed to meet the class specified:



Class I: Sheet polyethylene, nonperforated aluminum foil

Class II: Kraft-faced fiberglass batts or paint with a perm rating greater than 0.1 and less than or equal to 1.0

Class III: Latex or enamel paint


1405.3.3 Minimum clear airspaces and vented openings for vented cladding. For the purposes of this section, vented cladding shall include the following minimum clear airspaces.

1. Vinyl lap or horizontal aluminum siding applied over a weather-resistive barrier as specified in this chapter.
2. Brick veneer with a clear airspace as specified in this code.
3. Other approved vented claddings.



ENVELOPE MOISTURE

Sensor Locations




HAMPSHIRE COLLEGE | R.W. KERN CENTER



Bruner/Cott
architects and planners

ENVELOPE MOISTURE


% Wood Moisture Content



ENVELOPE MOISTURE

Calibrate for Temperature


“...add 1/2% for every 5 °C below 20°C...”



ENVELOPE MOISTURE


Financial Aid Suite

20% Wood Moisture



ENVELOPE MOISTURE

Relative Humidity



ENERGY MODEL



HAMPSHIRE COLLEGE | R.W. KERN CENTER



Bruner/Cott
architects and planners

ENERGY MODEL

- NREL's Energy-10 was the modeling software – two zone maximum, aimed at light commercial buildings



ENERGY MODEL

- NREL's Energy-10 was the modeling software – two zone maximum, aimed at light commercial buildings
- There were 7 occupancy types, combined into public and office zones, with schedules for occupancy, lights, plug loads



ENERGY MODEL

- NREL's Energy-10 was the modeling software – two zone maximum, aimed at light commercial buildings
- There were 7 occupancy types, combined into public and office zones, with schedules for occupancy, lights, plug loads
- I did pre-processing in Excel for ventilation, lighting, daylighting, and plug loads, and iterated E-10 to get the “right” output



ENERGY MODEL

- NREL's Energy-10 was the modeling software – two zone maximum, aimed at light commercial buildings
- There were 7 occupancy types, combined into public and office zones, with schedules for occupancy, lights, plug loads
- I did pre-processing in Excel for ventilation, lighting, daylighting, and plug loads, and iterated E-10 to get the “right” output
- Heating was post-processed with an estimated COP



PRE-PROCESSING LIGHTING ENERGY

	Area	W/sf	Hours/wk	kWh, lights full on	% daylit area	% daylight available	Potential % daylit	Occupancy factor	Total factor	kWh after daylight
Admissions	3,860	0.7	60	8,430	80%	60%	48%	70%	36%	3,069
Hampstore	2,400	1.1	60	8,237	10%	60%	6%	100%	94%	7,743
NSP	465	0.7	60	1,016	60%	60%	36%	85%	54%	552
Living	500	0.7	60	1,092	70%	60%	42%	100%	58%	633
Lobby/Gallery/coffee	3,500	0.5	90	8,190	50%	45%	23%	100%	78%	6,347
SLS	1,600	0.7	90	5,242	50%	45%	23%	75%	58%	3,047
Info	790	0.7	90	2,588	70%	45%	32%	80%	55%	1,418
	13,115			34,794						22,809



PRE-PROCESSING PLUG LOADS



HAMPSHIRE COLLEGE | R.W. KERN CENTER



Bruner/Cott
architects and planners

PRE-PROCESSING PLUG LOADS

- Similar to lighting



PRE-PROCESSING PLUG LOADS

- Similar to lighting
- W/sf continuous for each space (copiers, printers, etc.)



PRE-PROCESSING PLUG LOADS

- Similar to lighting
- W/sf continuous for each space (copiers, printers, etc.)
- W/person based on occupancy type and schedule



PRE-PROCESSING PLUG LOADS

- Similar to lighting
- W/sf continuous for each space (copiers, printers, etc.)
- W/person based on occupancy type and schedule
- W for café, Clivus, rainwater pump, effluent pump, UV water treatment, miscellaneous



PRE-PROCESSING PLUG LOADS

- Similar to lighting
- W/sf continuous for each space (copiers, printers, etc.)
- W/person based on occupancy type and schedule
- W for café, Clivus, rainwater pump, effluent pump, UV water treatment, miscellaneous
- Energy usage for ERVs calculated based on occupancy and wattage of each unit

